REVISED 09/09/2026 - floor area 696 sq ft - equipment RJPL-A042JK000 (3.5 ton). Hand-calculated revision - NOT certified Righ

Load Short Form
Entire House

Job: 2141 Date: FEBRUARY 2026
By: E

Project Information

For: JAY, PROFESSIONAL CAD DESIGN
PLAN SINGLE UNIT , PHOENIX,
AZ Phone: 623-249-1025

Design Information

	Htg	Clg
Outside db (°F)	*37*	108
Inside db (°F)	70	75
Design TD (°F)	33	33
Daily range	-	M
Inside humidity (%)	30	45
Moisture difference (gr/lb)	7	-7

Infiltration

Method	Simplified
Construction quality	Average
Fireplaces	0

HEATING EQUIPMENT

Make	Rheem	
Trade	RHEEM	
Model	RJPL-A042JK000	
AHRI ref	TBD	
Efficiency	8 HSPF	
Heating input		
Heating output	40000	Btuh @ 47°F
Temperature rise	34	°F
Actual air flow	1120	cfm
Air flow factor	0.095	cfm/Btuh
Static pressure	0.50	in H2O
Space thermostat		
Capacity balance point = 10 °F		

COOLING EQUIPMENT

Make	Rheem	
Trade	RHEEM	
Cond	RJPL-A042JK000	
Coil		
AHRI ref	TBD	
Efficiency	11.6 EER, 14 SEER	
Sensible cooling	31750	Btuh
Latent cooling	10250	Btuh
Total cooling	42000	Btuh
Actual air flow	1400	cfm
Air flow factor	0.052	cfm/Btuh
Static pressure	0.50	in H2O
Load sensible heat ratio	0.97	

ROOM NAME	Area (ft²)	Htg load (Btuh)	Clg load (Btuh)	Htg AVF (cfm)	Clg AVF (cfm)
BEDROOM 1	117	1955	2654	185	139
BEDROOM 2	117	1343	2247	127	118
LAUNDRY	34	803	1216	76	64
BATH	52	501	370	48	19
LIVING ROOM	162	4522	12993	428	682
KITCHEN	214	2705	7198	256	378

Bold/italic values have been manually overridden

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

Entire House Other equip loads Equip. @ 1.00 RSM Latent cooling	696	11822 1569	26679 1574 28253 984	1120	1400
TOTALS	696	13391	29237	1120	1400

Bold/italic values have been manually overridden

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

TRUE CALCS

Building Analysis
Entire House

Job: 2141 Date: FEBRUARY 2026
By: E

Project Information

For: JAY, PROFESSIONAL CAD DESIGN
PLAN SINGLE UNIT , PHOENIX,
AZ Phone: 623-249-1025

Design Conditions

Location:
Phoenix, AZ, US
Elevation: 1112 ft
Latitude: 33 °N

Outdoor:	**Heating**	**Cooling**
Dry bulb (°F)	*37*	108
Daily range (°F)	-	22 (M)
Wet bulb (°F)	-	70
Wind speed (mph)	15.0	7.5

Indoor:	**Heating**	**Cooling**
Indoor temperature (°F)	70	75
Design TD (°F)	33	33
Relative humidity (%)	30	45
Moisture difference (gr/lb)	7.1	-7.3

Infiltration:

Method	Simplified
Construction quality	Average
Fireplaces	0

Heating

Component	Btuh/ft²	Btuh	% of load
Walls	2.2	1436	10.7
Glazing	14.6	2830	21.1
Doors	12.9	270	2.0
Ceilings	1.0	668	5.0
Floors	0.6	390	2.9
Infiltration	2.6	2221	16.6
Ducts		4007	29.9
Piping		0	0
Humidification		0	0
Ventilation		1569	11.7
Adjustments		0	
Total		**13391**	**100.0**



Cooling

Component	Btuh/ft²	Btuh	% of load
Walls	2.3	1499	5.3
Glazing	54.6	10591	37.5
Doors	17.0	357	1.3
Ceilings	1.1	786	2.8
Floors	0.6	390	1.4
Infiltration	1.4	1168	4.1
Ducts		7348	26.0
Ventilation		1574	5.6
Internal gains		4540	16.1
Blower		0	0
Adjustments		0	
Total		**28253**	**100.0**



Latent Cooling Load = 984 Btuh
Overall U-value = 0.082 Btuh/ft²-°F

WARNING: window to floor area ratio = 27.9% - more than 25%.

Bold/italic values have been manually overridden

TRUE CALCS

Project Summary
Entire House

Job: 2141 Date: FEBRUARY 2026
By: E

Project Information

For: JAY, PROFESSIONAL CAD DESIGN
PLAN SINGLE UNIT , PHOENIX,
AZ Phone: 623-249-1025

Notes:

Design Information

Weather: Phoenix, AZ, US

Winter Design Conditions

Outside db	*37*	°F
Inside db	70	°F
Design TD	33	°F

Heating Summary

Structure	7815	Btuh
Ducts	4007	Btuh
Central vent (45 cfm)	*1569*	Btuh
Outside air		
Humidification	0	Btuh
Piping	0	Btuh
Equipment load	13391	Btuh

Infiltration

Method	Simplified
Construction quality	Average
Fireplaces	0

	Heating	Cooling
Area (ft²)	696	696
Volume (ft³)	6264	6264
Air changes/hour	0.61	0.32
Equiv. AVF (cfm)	64	33

Summer Design Conditions

Outside db	108	°F
Inside db	75	°F
Design TD	33	°F
Daily range	M	
Relative humidity	45	%
Moisture difference	-7	gr/lb

Sensible Cooling Equipment Load Sizing

Structure	19331	Btuh
Ducts	7348	Btuh
Central vent (45 cfm)	*1574*	Btuh
Outside air		
Blower	0	Btuh
Use manufacturer's data	y	
Rate/swing multiplier	1.00	
Equipment sensible load	28253	Btuh

Latent Cooling Equipment Load Sizing

Structure	1341	Btuh
Ducts	-141	Btuh
Central vent (45 cfm)	*-216*	Btuh
Outside air		
Equipment latent load	984	Btuh
Equipment Total Load (Sen+Lat)	29237	Btuh
Req. total capacity at 0.70 SHR	3.4	ton

Heating Equipment Summary

Make	Rheem
Trade	RHEEM
Model	RJPL-A042JK000
AHRI ref	TBD

Efficiency	8 HSPF	
Heating input		
Heating output	40000	Btuh @ 47°F
Temperature rise	34	°F
Actual air flow	1120	cfm
Air flow factor	0.095	cfm/Btuh
Static pressure	0.50	in H2O
Space thermostat		

Capacity balance point = 10 °F

Cooling Equipment Summary

Make	Rheem
Trade	RHEEM
Cond	RJPL-A042JK000
Coil	
AHRI ref	TBD

Efficiency	11.6 EER, 14 SEER	
Sensible cooling	31750	Btuh
Latent cooling	10250	Btuh
Total cooling	42000	Btuh
Actual air flow	1400	cfm
Air flow factor	0.052	cfm/Btuh
Static pressure	0.50	in H2O
Load sensible heat ratio	0.97	

Bold/italic values have been manually overridden

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

AED Assessment
Entire House

Job: 2141 Date: FEBRUARY 2026
By: E

Project Information

For: JAY, PROFESSIONAL CAD DESIGN
PLAN SINGLE UNIT , PHOENIX,
AZ Phone: 623-249-1025

Design Conditions

Location:
Phoenix, AZ, US
Elevation: 1112 ft
Latitude: 33 °N

Outdoor:

	Heating	Cooling
Dry bulb (°F)	*37*	108
Daily range (°F)	-	22 (M)
Wet bulb (°F)	-	70
Wind speed (mph)	15.0	7.5

Indoor:

	Heating	Cooling
Indoor temperature (°F)	70	75
Design TD (°F)	33	33
Relative humidity (%)	30	45
Moisture difference (gr/lb)	7.1	-7.3

Infiltration:

Test for Adequate Exposure Diversity



Maximum hourly glazing load exceeds average by 52.1%.

House does not have adequate exposure diversity (AED), based on AED limit of 30%.

AED excursion: 1687 Btuh (PFG - 1.3*AFG)

Bold/italic values have been manually overridden

REVISED 09/09/2026 - floor area 696 sq ft - equipment RJPL-A042JK000 (3.5 ton). Hand-calculated revision - NOT certified Right-Suite

TRUE CALCS

Right-J® Worksheet
Entire House

Job: **2141**
Date:
FEBRUARY 2026
By: E

		Entire House	BEDROOM 1
1	Room name	Entire House	BEDROOM 1
2	Exposed wall	95.0 ft	19.3 ft
3	Room height	9.0 ft	9.0 ft heat/cool
4	Room dimensions		10.0 x 11.7 ft
5	Room area	696.0 ft²	117.0 ft²

	Ty	Construction number	U-value (Btuh/ft²-°F)	Or	HTM (Btuh/ft²) Heat	HTM (Btuh/ft²) Cool	Entire House Area (ft²) or perimeter (ft) Gross	Entire House N/P/S	Entire House Load (Btuh) Heat	Entire House Load (Btuh) Cool	Bedroom 1 Area (ft²) or perimeter (ft) Gross	Bedroom 1 N/P/S	Bedroom 1 Load (Btuh) Heat	Bedroom 1 Load (Btuh) Cool
6	W	12E-0sw	0.068	n	2.24	2.34	180	159	357	372	83	83	187	195
.	└─D	11D0	0.390	n	12.87	16.98	21	21	270	357	0	0	0	0
.	W	12E-0sw	0.068	e	2.24	2.34	248	198	443	463	90	65	146	152
.	└─G	PHX MINS	0.400	e	13.20	37.16	50	0	660	1858	25	0	330	929
11	W	12E-0sw	0.068	s	2.24	2.34	180	180	404	422	0	0	0	0
	W	12E-0sw	0.068	w	2.24	2.34	248	104	232	242	0	0	0	0
	└─G	1D-c2ovd	0.570	w	18.81	72.46	48	0	903	3478	0	0	0	0
	└─G	PHX MINS	0.400	w	13.20	37.16	96	0	1267	3568	0	0	0	0
	C	18A-38zd	0.029	-	0.96	1.13	696	696	668	786	117	117	112	132
	F	19C-19cscp	0.049	-	0.56	0.56	696	696	390	390	117	117	66	66

			Entire House Gross	Entire House N/P/S	Entire House Heat	Entire House Cool	Bedroom 1 Gross	Bedroom 1 N/P/S	Bedroom 1 Heat	Bedroom 1 Cool
6	c) AED excursion					1687				-63
	Envelope loss/gain				5594	13623			841	1411
12	a) Infiltration				2221	1168			451	237
	b) Room ventilation				0	0			0	0
13	Internal gains:	Occupants @ 230	3			690	0			0
		Appliances/other				3850				275
	Subtotal (lines 6 to 13)				7815	19331			1292	1923
	Less external load				0	0			0	0
	Less transfer				0	0			0	0
	Redistribution				0	0			0	0
14	Subtotal				7815	19331			1292	1923
15	Duct loads		51%	38%	4007	7348	51%	38%	663	731
	Total room load				11822	26679			1955	2654
	Air required (cfm)				1120	1400			185	139

REVISED 09/09/2026 - floor area 696 sq ft - equipment RJPL-A042JK000 (3.5 ton). Hand-calculated revision - NOT certified Right-Suite

Right-J® Worksheet
Entire House

Job: 2141
Date:
FEBRUARY 2026
By: E

				BEDROOM 2				LAUNDRY			
1	Room name			BEDROOM 2				LAUNDRY			
2	Exposed wall			10.0 ft				11.0 ft			
3	Room height			9.0 ft		heat/cool		9.0 ft		heat/cool	
4	Room dimensions			10.0 x 11.7 ft				7.5 x 4.5 ft			
5	Room area			117.0 ft²				34.0 ft²			

	Ty	Construction number	U-value (Btuh/ft²-°F)	Or	HTM (Btuh/ft²) Heat	HTM (Btuh/ft²) Cool	Area (ft²) or perimeter (ft) Gross	N/P/S	Load (Btuh) Heat	Load (Btuh) Cool	Area (ft²) or perimeter (ft) Gross	N/P/S	Load (Btuh) Heat	Load (Btuh) Cool
6	W	12E-0sw	0.068	n	2.24	2.34	0	0	0	0	0	0	0	0
.	└D	11D0	0.390	n	12.87	16.98	0	0	0	0	0	0	0	0
.	W	12E-0sw	0.068	e	2.24	2.34	90	65	146	152	68	68	151	158
.	└G	PHX MINS	0.400	e	13.20	37.16	25	0	330	929	0	0	0	0
11	W	12E-0sw	0.068	s	2.24	2.34	0	0	0	0	32	32	71	74
	W	12E-0sw	0.068	w	2.24	2.34	0	0	0	0	0	0	0	0
	└G	1D-c2ovd	0.570	w	18.81	72.46	0	0	0	0	0	0	0	0
	└G	PHX MINS	0.400	w	13.20	37.16	0	0	0	0	0	0	0	0
	C	18A-38zd	0.029	-	0.96	1.13	117	117	112	132	34	34	33	38
	F	19C-19cscp	0.049	-	0.56	0.56	117	117	66	66	34	34	19	19

			BEDROOM 2 Gross	N/P/S	Heat	Cool	LAUNDRY Gross	N/P/S	Heat	Cool
6	c) AED excursion					-49				-43
	Envelope loss/gain				654	1230			274	246
12	a) Infiltration				234	123			257	135
	b) Room ventilation				0	0			0	0
13	Internal gains:	Occupants @ 230	0			0	0			0
		Appliances/other				275				500
	Subtotal (lines 6 to 13)				888	1628			531	881
	Less external load				0	0			0	0
	Less transfer				0	0			0	0
	Redistribution				0	0			0	0
14	Subtotal				888	1628			531	881
15	Duct loads		51%	38%	455	619	51%	38%	272	335
	Total room load				1343	2247			803	1216
	Air required (cfm)				127	118			76	64

REVISED 09/09/2026 - floor area 696 sq ft - equipment RJPL-A042JK000 (3.5 ton). Hand-calculated revision - NOT certified Right-Suite

Right-J® Worksheet
Entire House

Job: 2141
Date:
FEBRUARY 2026
By: E

		BATH				LIVING ROOM			
1	Room name	BATH				LIVING ROOM			
2	Exposed wall	5.8 ft				27.5 ft			
3	Room height	9.0 ft		heat/cool		9.0 ft		heat/cool	
4	Room dimensions	7.5 x 6.9 ft				15.0 x 10.8 ft			
5	Room area	52.0 ft²				162.0 ft²			

	Ty	Construction number	U-value (Btuh/ft²-°F)	Or	HTM (Btuh/ft²) Heat	HTM Cool	BATH Area (ft²) or perimeter (ft) Gross	BATH N/P/S	BATH Load (Btuh) Heat	BATH Load Cool	LIVING ROOM Area (ft²) or perimeter (ft) Gross	LIVING ROOM N/P/S	LIVING ROOM Load (Btuh) Heat	LIVING ROOM Load Cool
6	W	12E-0sw	0.068	n	2.24	2.34	0	0	0	0	97	76	170	177
.	└──D	11D0	0.390	n	12.87	16.98	0	0	0	0	21	21	270	357
.	W	12E-0sw	0.068	e	2.24	2.34	0	0	0	0	0	0	0	0
.	└──G	PHX MINS	0.400	e	13.20	37.16	0	0	0	0	0	0	0	0
11	W	12E-0sw	0.068	s	2.24	2.34	52	52	116	121	0	0	0	0
	W	12E-0sw	0.068	w	2.24	2.34	0	0	0	0	151	55	123	128
	├──G	1D-c2ovd	0.570	w	18.81	72.46	0	0	0	0	48	0	903	3478
	└──G	PHX MINS	0.400	w	13.20	37.16	0	0	0	0	48	0	634	1784
	C	18A-38zd	0.029	-	0.96	1.13	52	52	50	59	162	162	156	183
	F	19C-19cscp	0.049	-	0.56	0.56	52	52	29	29	162	162	91	91

			BATH Gross	BATH N/P/S	BATH Heat	BATH Cool	LIVING ROOM Gross	LIVING ROOM N/P/S	LIVING ROOM Heat	LIVING ROOM Cool
6	c) AED excursion					-12				1519
	Envelope loss/gain				195	197			2346	7717
12	a) Infiltration				136	71			643	338
	b) Room ventilation				0	0			0	0
13	Internal gains:	Occupants @ 230	0			0	2			460
		Appliances/other				0				900
	Subtotal (lines 6 to 13)				331	268			2989	9415
	Less external load				0	0			0	0
	Less transfer				0	0			0	0
	Redistribution				0	0			0	0
14	Subtotal				331	268			2989	9415
15	Duct loads		51%	38%	170	102	51%	38%	1533	3578
	Total room load				501	370			4522	12993
	Air required (cfm)				48	19			428	682

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

TRUE CALCS

Right-J® Worksheet
Entire House

Job: 2141
Date:
FEBRUARY 2026
By: E

1	Room name							KITCHEN								
2	Exposed wall							21.5 ft								
3	Room height							9.0 ft		heat/cool						
4	Room dimensions							19.8 x 10.8 ft								
5	Room area							214.0 ft²								
	Ty	Construction number	U-value (Btuh/ft²-°F)	Or	HTM (Btuh/ft²)		Area (ft²) or perimeter (ft)		Load (Btuh)		Area or perimeter		Load			
					Heat	Cool	Gross	N/P/S	Heat	Cool	Gross	N/P/S	Heat	Cool		
6	W	12E-0sw	0.068	n	2.24	2.34	0	0	0	0						
.	└D	11D0	0.390	n	12.87	16.98	0	0	0	0						
.	W	12E-0sw	0.068	e	2.24	2.34	0	0	0	0						
.	└G	PHX MINS	0.400	e	13.20	37.16	0	0	0	0						
11	W	12E-0sw	0.068	s	2.24	2.34	97	97	217	227						
	W	12E-0sw	0.068	w	2.24	2.34	97	49	109	114						
	├G	1D-c2ovd	0.570	w	18.81	72.46	0	0	0	0						
	└G	PHX MINS	0.400	w	13.20	37.16	48	0	634	1784						
	C	18A-38zd	0.029	-	0.96	1.13	214	214	205	242						
	F	19C-19cscp	0.049	-	0.56	0.56	214	214	120	120						
6	c) AED excursion									335						
	Envelope loss/gain								1285	2822						
12	a) Infiltration								503	264						
	b) Room ventilation								0	0						
13	Internal gains:		Occupants @		230		1			230						
			Appliances/other							1900						
	Subtotal (lines 6 to 13)								1788	5216						
	Less external load								0	0						
	Less transfer								0	0						
	Redistribution								0	0						
14	Subtotal								1788	5216						
15	Duct loads						51%	38%	917	1982						
	Total room load								2705	7198						
	Air required (cfm)								256	378						

Calculations approved by ACCA to meet all requirements of Manual J 8th Ed.

TRUE CALCS

Manual S Compliance Report

Entire House

Job: 2141 Date: FEBRUARY 2026
By: E

Project Information

For: JAY, PROFESSIONAL CAD DESIGN
PLAN SINGLE UNIT PHOENIX,
AZ Phone: 623-249-1025

Cooling Equipment

Design Conditions

Outdoor design DB:	108 °F	Sensible gain:	28253 Btuh	Entering coil DB:	79.0 °F
Outdoor design WB:	69.9 °F	Latent gain:	984 Btuh	Entering coil WB:	62.1 °F
Indoor design DB:	75.0 °F	Total gain:	29237 Btuh		
Indoor RH:	45 %	Estimated airflow:	1400 cfm		

Manufacturer's Performance Data at Actual Design Conditions

Equipment type: Pkg ASHP
Manufacturer: Rheem Model: RJPL-A042JK000
Actual airflow: 1400 cfm
Sensible capacity: 33266 Btuh 118 % of load
Latent capacity: 1099 Btuh 112 % of load
Total capacity: 34364 Btuh 118 % of load SHR: 97 %

Heating Equipment

Design Conditions

Outdoor design DB:	37.0 °F	Heat loss:	13391 Btuh	Entering coil DB:	67.5 °F
Indoor design DB:	70.0 °F				

Manufacturer's Performance Data at Actual Design Conditions

Equipment type: Pkg ASHP
Manufacturer: Rheem Model: RJPL-A042JK000
Actual airflow: 1120 cfm
Output capacity: 34032 Btuh 254 % of load
Supplemental heat required: 0 Btuh

Capacity balance: 10 °F
Economic balance: -99 °F

REVIEW: total cooling capacity = 118% of load. ACCA Manual S limit is 115%.

TRUE CALCS

Static Pressure and Friction Rate

Entire House

Job: 2141 Date: FEBRUARY 2026
By: E

Project Information

For: JAY, PROFESSIONAL CAD DESIGN
PLAN SINGLE UNIT , PHOENIX,
AZ Phone: 623-249-1025

Available Static Pressure

	Heating (in H2O)	Cooling (in H2O)
External static pressure	0.50	0.50
Pressure losses		
Coil	0.19	0.19
Heat exchanger	0	0
Supply diffusers	0.04	0.04
Return grilles	0.04	0.04
Filter	0.11	0.11
Humidifier	0	0
Balancing damper	0	0
Other device	0	0
Available static pressure	0.12	0.12

Total Effective Length

	Supply (ft)	Return (ft)
Measured length of run-out	11	4
Measured length of trunk	7	0
Equivalent length of fittings	145	60
Total length	162	64
Total effective length		226

Friction Rate

	Heating (in/100ft)		Cooling (in/100ft)	
Supply Ducts	0.053	NOT OK	0.053	NOT OK
Return Ducts	0.053	NOT OK	0.053	NOT OK

Fitting Equivalent Length Details

Supply 4AD=60, 11T=25, 11T=25, 1A=35: TotalEL=145

Return 5D=40, 6M=20: TotalEL=60

TRUE CALCS

Duct System Summary
Entire House

Job: 2141 **Date:** FEBRUARY 2026
By:

Project Information

For: JAY, PROFESSIONAL CAD DESIGN
PLAN SINGLE UNIT , PHOENIX,
AZ Phone: 623-249-1025

	Heating		Cooling	
External static pressure	0.50	in H2O	0.50	in H2O
Pressure losses	0.38	in H2O	0.38	in H2O
Available static pressure	0.12	in H2O	0.12	in H2O
Supply / return available pressure	0.086 / 0.034	in H2O	0.086 / 0.034	in H2O
Lowest friction rate	0.053	in/100ft	0.053	in/100ft
Actual air flow	1120	cfm	1400	cfm
Total effective length (TEL)		226 ft		

Supply Branch Detail Table

Name		Design (Btuh)	Htg (cfm)	Clg (cfm)	Design FR	Diam (in)	H x W (in)	Duct Matl	Actual Ln (ft)	Ftg.Eqv Ln (ft)	Trunk
BATH	h	501	48	19	0.055	6.0	0x 0	VIFx	12.4	145.0	st3
BEDROOM 1	h	1955	185	139	0.053	10.0	0x 0	VIFx	17.3	145.0	st1
BEDROOM 2	h	1343	127	118	0.056	10.0	0x 0	VIFx	9.8	145.0	st1
KITCHEN	c	3599	128	189	0.085	10.0	0x 0	VIFx	6.2	95.0	
KITCHEN-A	c	3599	128	189	0.086	10.0	0x 0	VIFx	4.7	95.0	
LAUNDRY	h	803	76	64	0.054	7.0	0x 0	VIFx	14.6	145.0	st3
LIVING ROOM	c	6497	214	341	0.069	12.0	0x 0	VIFx	3.9	120.0	st2
LIVING ROOM-B	c	6496	214	341	0.067	12.0	0x 0	VIFx	9.3	120.0	st2

Supply Trunk Detail Table

Name	Trunk Type	Htg (cfm)	Clg (cfm)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Duct Material	Trunk
st2	Peak AVF	428	682	0.066	489	16.0	0 x 0	VinlFlx	
st3	Peak AVF	124	83	0.054	227	10.0	0 x 0	VinlFlx	st1
st1	Peak AVF	436	340	0.053	408	14.0	0 x 0	VinlFlx	

Return Branch Detail Table

Name	Grille Size (in)	Htg (cfm)	Clg (cfm)	TEL (ft)	Design FR	Veloc (fpm)	Diam (in)	H x W (in)	Stud/Joist Opening (in)	Duct Matl	Trunk
rb1	0x 0	1120	1400	63.8	0.053	530	22.0	0x 0		VIFx	

REVISED 09/09/2026 - floor area 696 sq ft - equipment RJPL-A042JK000 (3.5 ton). Hand-calculated revision - NOT certified Righ



1ST FLOOR



Job #: 2141
Performed by Evan for:
JAY
PLAN SINGLE UNIT
PHOENIX, AZ
Phone: 623-249-1025

Scale: 1 : 46
Page 1
Right-Suite® Universal 2019
19.0.09 RSU23025
2021-feb-2416:42:03
...\JAY (BOSCO) PLANSINGLE UNIT .

REVISED 09/09/2026 - floor area 696 sq ft - equipment RJPL-A042JK000 (3.5 ton). Hand-calculated revision - NOT certified Righ

2 ND STORY



Job #: 2141
Performed by Evan for:
JAY
PLAN SINGLE UNIT
PHOENIX, AZ
Phone: 623-249-1025

Scale: 1 : 46

Right-Suite® Universal 2019
19.0.09 RSU23025
2019-Aug-19 16:42:03
...\JAY (BOSCO) PLAN SINGLE UNIT ....